



Mastering AVI

Part 4: Selection and purchasing of an automated inspection system

- Technical requirements
- Integration into existing processes, lines/ machines and systems
- Cost and effort considerations
- Risk Assessment



Instructor Lead: Romain Veillon / Fernand Koert / Sébastien Koch





Where to start?



- When procurement of AVI machine is foreseen, you may consider all these aspects:
- User Requirements, typically the URS document
- Engineering specifications
- EHS rules
- Contractual terms
 - Payment terms / conditions
 - Project mngt / key milestones
 - Target KPIs
 - Training
 - Key milestones (commisioning / validation / ramp up)
 - Performance based contract
















Some challenges



Cost / Payback











Company culture

What are Silos in your company?



- Production
- Maintenance
- Engineering
- Procurement
- QA
- QC
- RA
- PMOs
- EHS: Ergonomic

• ...

1 URS+1 Contract





Topics to cover in URS

| URS | Eng. Spec. | Contracts |
|--|--------------|-------------------------|
| ✓ User needs | √ electrical | ✓ R&R |
| ✓ Products | ✓ Pneumatic | ✓ certifications |
| ✓ Prim. packaging | ✓ Automation | ✓ Document approval |
| ✓ KPIs | ✓ EHS | ✓ User |
| ✓ Kits | ✓ Layout | ✓ KPIs target |
| ✓ validation | ✓ utilities | ✓ Payment terms |
| ✓ documentation | | ✓ Key milestones |
| ✓ training | | ✓ KM |
| ✓ maintenance | | ✓ Commissioning FAT SAT |
| ✓ Spare part + ERES + Alarm✓ Automation | | ✓ Support mentoring |






Integration into existing process

Where does it fit in?



- Inline after Filling
- Standalone "island concept"
- Before labelling
- Or all in one line / feedback or bottlenecking?
- How to maintain clean room conditions
- When integrated in existing line
 - How to connect the parts
 - Who will be responsible for this
 - What about AQL sampling: manual, automatic




→ Need to build a Business Process Mapping






Business Process Mapping







Need for SIPOC before Deep Dive into details







Integration into existing processes

- Online versus offline:
 - Inline after filling
 - More appropriate in case cold chain
 - But influenced by process circumstances before
 - Offline
 - Independent of the process circumstances before
 - But more labor
 - More handling, more risks, e.g. Mix-ups



Product behavior

- Viscous. If so the introduction of air bubbles is likely
- Humans can distinct air bubbles from particles far better
- Offline would be more appropriate







Integration into existing process

Product behavior

- If your products are a mix of waterlike to viscous
- Make it two ways. Partly inline, partly offline





AVI in general

- These machines are complex
- They may go in error
- you might be confronted with unexpected high ejects
- Buffering and offline inspection should be considered






Some Prerequisites

Representative test kits are prepared

- Defect units (defined and stable)
- Worst case
 - Product and/or container
- Good units





MVI results on these test kits are known

- Statistical results, e.g. through Knapp Kushner
- Human limits
 - Particle size
 - Areas not easy to inspect





Considerations when Selecting

There are only few mayor machine suppliers
Your URS and engineering specs are the basis

- The machine supplier must meet these requirements / time /Cost
- The statistical result on these test kits must be equal or better than MVI





AVI must perform equal or better than MVI

- How much better
- Against what costs
- Is manual inspection of AVI ejects allowed
- AVI is not perfect
- 100% detection of everything not wanted is impossible





Total Cost?



Mechanical you can get everything

- OEM (Original Equipment Manufacturer)
- Third parties
- Unlimited in time

Apart from wanted performance, machine price only

- Printers are sold at/or below cost price
 - They earn in selling ink
- What about spare parts
 - · What do you minimal need
 - Life cycle?
 - Costs?
 - Total Cost of Ownership
 - Resources on project to secure planning







Considerations when Selecting

Electrically

- · Lifecycle is short
- · Ongoing development is rapid
- Older parts become obsolete in short time
- · Availability is limited in time
- Machine suppliers often don't produce these parts, they buy on the market
- Certification by geographic area Eur / US / Can / JP





Cameras/LEDs

Innovation vs long term solutions

Machine supplier guaranties

- Spare parts are available for 10 ? 15 years?
- Equal with LEDs and cameras?





Supplier decision matrix

- ☐ Technical & Engineering Design
- □ Performance
- □ Automation
- □ Quality
- ☐ EHS Process Safety
- ☐ Commercial Support






Why a Business Process Mapping?





Mapping of information flow

Focus VI entire Process not only AVI equipment








Business Process Mapping

• And move forward to elaborate a fully transparent flow of information inside AVI



Automation

Mechanic

Vision






Still a V Model? => No





Qualification Path with QbD



Key learning: GSK new validation framework puts strong effort on initial RA and DQ IQ OQ test must only mitigate risk identified during RA no additional test must be done if not critical

IQ OQ test may be driven by RA and GMP UR





Why Risk Assessment is key?







Process System Risk Assessment

- 1. Divide the process is sub process steps
 - ✓ Prerequisite
 - ✓ Warehousing
 - √ Handling unit Deconditioning
 - ✓ AVI ——
 - ✓ Leak Testing (if any)
 - √ AVI control strategy
 - √ Handling unit reconditioning
 - √ 2nd stage (if any)
 - ✓ MVI Control Strategy (AQL+trend chart)
 - ✓ End of operations

Unit presentation to camera by mechanical handling

Unit presentation to camera with product rotation

Unit presentation to camera with glass & product dependent

parameters

Refeed transport mode

Lightning to camera

Image acquisition

Digital Image Processing

Result transfer to shift register

Physical unit ejection

Inspection result archiving (SQL)

Functional test kit, after operations

Batch closure and local report creation

Central reporting & archiving





Risk Assessment

Identify CQA CPP and Critical Design Elements

✓ Some CQAs for VI

| Atributes | | | | | | | | | |
|-----------|---|-----------------|------------------------|---------------------|------------------------------|--------------------------|--|--|--|
| CQA | CQA | CQA | CQA | CQA | CQA | PA | | | |
| Identity | Essentialy free of glass Defect/Particles/Stopper defect/Closure defec. fill level/Empty/Lyo defect | Leak absence | Container Integrity | Stength, Potency | Potency (sheer stress) | Equipment Performance | | | |

- √ If at least 1 CQA is impacted the parameters becomes a CPP
- ✓ Data criticality has to be evaluated, Critical design element explored with supplier + list of alarms





Risk Assessment


Identify the risk (unwanted event / cause / consequence)
Example

| Phase 1 : Process Analysis | | Phase 2: Risk Identification & Evaluation | | | | | |
|----------------------------|--------------|---|---|--------------------------------------|--|---|--|
| | Process Step | Process Sub- Step/Description | Parameter or critical aspect | Unwanted events | | | |
| # | | | | Unwanted event description | Because of | With the consequences | |
| 1 | Prerequisite | Set up AVI recipe loading | Recipe name and versioning choice for all sub-config (motion, light, handling, image processing), and product | Wrong selection of recipe parameters | Previous recipe available for selection | Use of wrong parameters for lot inspection | |






Risk Ass. can mitigate risks in multiples pathways : not only IQ OQ PQ








Risk Assessment: Risk control







Design your qualification:



Installation Qualification

 Documentation verification, component data verification, drawings, system Installation verification, utilities, Software and IT verification

Operational Qualification

- HMI Layout verification
- Alarms verification
- Screen navigation, access verification, security verification
- ER/ES verification (electronic Records and signatures)
- MES (Manufacturing Execution System) server communication
- Backup / Restore and disaster recovery
- Containers handling
- Counters and cells control
- VI critical parameter control (baseline)
- Recipes version verification
-not exhaustive list





FAT

- Should not be on user site
- Use supplier facilities / competencies
- If not passed
 - Due to minor issues
 - Due to mayor issues
- Never expect it will be solved during SAT
- ⇒ Punch list is key at supplier site
- ⇒ All key resources are at supplier site Do not postpone









You have learnt

URS

- Risk Assessment
- UR / Eng. spec. / Contracts
- Cost-Benefit / Patient / Delivery
- Silos vs Holistic URS
- Need for SIPOC / Business Mapping
- Risk assessment
- Business Process Mapping



URS

- Why do we distinct UR and TR
- What does SIPOC stand for
- Why is risk assessment key and which elements should be covered

