



MAY 2, 2024

---

# Navigating Capital Projects: WHEN AND HOW TO CONSIDER PREFABRICATED SOLUTIONS





*Molly Otter*

Director of Process  
Architecture

**GBA**  
LIFE SCIENCES

# Agenda

---

▶ **What are Prefabricated Solutions**

▶ **Advantages of Prefabricated**

▶ **What about stick built?**

▶ **How to Decide**

▶ **Case Study**

What are  
Prefabricated Solutions?

---

# ► PREFABRICATED SOLUTIONS



**EQUIPMENT**



**SOFT SIDED**



**PRECAST & PEMB**



**MODULAR WALLS & CEILINGS**



**PREFAB MODULAR BUILDING**



**PREFAB - DECON, AIRLOCKS**

# Advantages of Prefabricated Solutions

---

# ▶ ADVANTAGES

## INHIBIT ORGANIC GROWTH

- Non-porous
- Inherently antibacterial



# ▶ ADVANTAGES

## MAINTAIN EXISTING OPERATIONS

- Reduced construction particulates from grinding/welding, drywall dust
- Reduced onsite activities on infill projects
- Reduced laydown area
- Reduced ongoing maintenance





# ▶ ADVANTAGES

## LIFETIME COST SAVINGS

- Accelerated time to market
- Shop labor vs field labor
- Early detection and resolution
- Reduced ongoing maintenance
- Capital vs expense



# ▶ ADVANTAGES

## EXPERTISE AND CONSISTENCY

- Consistent workforce
- Construction tolerances 2-5% rework
- High quality labor



# ▶ ADVANTAGES

## SCHEULING

- Parallel fabrication
- Scheduled arrival of kitted parts
- Reduced CQV
- Enables timely access to lifesaving medications for patients



# ▶ ADVANTAGES

## IMPROVED SAFETY

- Controlled factory environments
- Walkable ceilings



# ▶ ADVANTAGES

## SCALABILITY

- “Design once, build twice”
- Expansion
- Technology
- Adaptability



What About  
Stick Built?

---

# STICK BUILT

Lowest first cost

How are you looking at cost?

- Initial cost vs lifetime cost
- Who is paying for the project



# STICK BUILT

INTEGRATION  
WITH EXISTING  
FACILITIES

LOCAL LABOR POOL

- Future modifications on your schedule






# STICK BUILT

## SCHEDULE CONSIDERATIONS

- Greenfield vs infill
- Critical Path and Long lead times



# How to Decide?

---



# ▶ LEVEL OF PROJECT DEFINITION

**30% to 40% of the cost of building a typical commercial building can be attributed to redesign and change orders resulting from issues identified during construction.**

*- Report from the National Institute of Standards and Technology (NIST)*





# Case Study

---



# PROJECT SCOPE

**INCREASED MARKET DEMAND  
FOR TIME CRITICAL VACCINE**



**Expansion for the  
2nd presentation  
of the vaccine**



**Additional  
compounding  
capacity**




**Existing product  
commitments**

# IDENTIFY THE OPTIONS

 WAREHOUSE

 INTERIOR RENOVATION

 EXPANSION





# FEASIBILITY EVALUATION

## WAREHOUSE

	Schedule			Host Facility				\$	Scope	
	Bandwidth	Greenfield v. Renovation	FAT	Operational Facility	Laydown Area	Construction Access	Own, Lease, Move	Cost	Program Definition	Process Flow
Stick Built	X	R		-	X	X		X	X	-
Modular 1	-	R				X				
PreFab 1	-	R		X	X	X	X	-	X	




# FEASIBILITY EVALUATION

■ WAREHOUSE

■ INTERIOR RENOVATION

		Schedule			Host Facility				\$	Scope	
		Bandwidth	Greenfield v. Renovation	FAT	Operational Facility	Laydown Area	Construction Access	Own, Lease, Move	Cost	Program Definition	Process Flow
■	Stick Built	X	R		-	X	X		X	X	-
■	Modular 1	-	R				X				
■	PreFab 1	-	R		X	X	X	X	-	X	
■	Stick Built	X	R		-	-			X		-
■	Modular 1	-	R		X	X	X		X	-	
■	PreFab 1	-	R				-		-		




# FEASIBILITY EVALUATION

■ WAREHOUSE

■ INTERIOR RENOVATION

■ EXPANSION

		Schedule			Host Facility				\$	Scope	
		Bandwidth	Greenfield v. Renovation	FAT	Operational Facility	Laydown Area	Construction Access	Own, Lease, Move	Cost	Program Definition	Process Flow
■	Stick Built	X	R		-	X	X		X	X	-
■	Modular 1	-	R				X				
■	PreFab 1	-	R		X	X	X	X	-	X	
■	Stick Built	X	R		-	-			X		-
■	Modular 1	-	R		X	X	X		X	-	
■	PreFab 1	-	R				-		-		
■	Stick Built	X	G		X	X	X		X	X	X
■	Modular 1	-	G		X	X	X		X	-	
■	PreFab 1	-	G		X	X	X		-	-	



# ▶ **DECISION**

## **EXPANSION**

**Adherence to site master plan**

## **METHOD**

**Stick built**

## **DECISION CRITERIA**

- **Evolving program**
- **Minimize disruption to ongoing manufacturing**
- **Balance between construction and operational function**
- **Access to utilities**



# BUILDING



# ► HYBRID SOLUTION

Modular wall panels were used in several areas to accommodate long lead equipment, valve changes, utility panels, HMI and point of use cabinets



*In Conclusion*

---

# ▶ IT DEPENDS

**How well defined is the program and process needs?**

**What sort of flexibility do I need for future expansions or modifications?**

**Is cost to be evaluated as initial cost or life cycle costs?**

**Does the initial investment justify a faster speed-to-market?**



# GBA

---

LIFE SCIENCES

